

United States Department of the Interior  
Heritage Conservation and Recreation Service

For HCRS use only  
received  
date entered

# National Register of Historic Places Inventory—Nomination Form

See instructions in *How to Complete National Register Forms*  
Type all entries—complete applicable sections

## 1. Name

historic Stevensville Bank

and/or common

## 2. Location

street & number Love Point Road (MD 18) n/a not for publication

city, town Stevensville n/a vicinity of congressional district First

state Maryland code 21 county Queen Anne's code 035

## 3. Classification

|   |  |   |  |
|---|--|---|--|
| <b>Category</b>                                 | <b>Ownership</b>                                   | <b>Status</b>                                       | <b>Present Use</b>                             |
| <input type="checkbox"/> district               | <input type="checkbox"/> public                    | <input checked="" type="checkbox"/> occupied        | <input type="checkbox"/> agriculture           |
| <input checked="" type="checkbox"/> building(s) | <input checked="" type="checkbox"/> private        | <input type="checkbox"/> unoccupied                 | <input checked="" type="checkbox"/> commercial |
| <input type="checkbox"/> structure              | <input type="checkbox"/> both                      | <input type="checkbox"/> work in progress           | <input type="checkbox"/> educational           |
| <input type="checkbox"/> site                   | <b>Public Acquisition</b>                          | <b>Accessible</b>                                   | <input type="checkbox"/> entertainment         |
| <input type="checkbox"/> object                 | <input type="checkbox"/> in process                | <input checked="" type="checkbox"/> yes: restricted | <input type="checkbox"/> government            |
|   | <input type="checkbox"/> being considered          | <input type="checkbox"/> yes: unrestricted          | <input type="checkbox"/> industrial            |
|   | <input checked="" type="checkbox"/> not applicable | <input type="checkbox"/> no                         | <input type="checkbox"/> military              |
|   |  |   | <input type="checkbox"/> museum                |
|   |  |   | <input type="checkbox"/> park                  |
|   |  |   | <input type="checkbox"/> private residence     |
|   |  |   | <input type="checkbox"/> religious             |
|   |  |   | <input type="checkbox"/> scientific            |
|   |  |   | <input type="checkbox"/> transportation        |
|   |  |   | <input type="checkbox"/> other:                |

## 4. Owner of Property

name Charles Marsteller

street & number Route 3, Box 268

city, town Stevensville n/a vicinity of state Maryland 21666

## 5. Location of Legal Description

courthouse, registry of deeds, etc. Queen Anne's County Courthouse

street & number Courthouse Square

city, town Centreville state Maryland

## 6. Representation in Existing Surveys

title Maryland Historical Trust  
Historic Sites Inventory

has this property been determined eligible? ☐ yes ☒ no

ate 1978

☐ federal ☒ state ☐ county ☐ local

depository for survey records 21 State Circle

city, town Annapolis state Maryland 21401

## 7. Description

QA-264

**Condition**

☒ excellent  
☐ good  
☐ fair

☐ deteriorated  
☐ ruins  
☐ unexposed

**Check one**

☐ unaltered  
☒ altered

**Check one**

☒ original site  
☐ moved date n/a

**Describe the present and original (if known) physical appearance**

**Number of Resources****Contributing**

1  
0  
0  
0  
1

**Noncontributing**

0 buildings  
0 sites  
1 structures  
0 objects

1 Total

Number of previously listed  
National Register properties  
included in this nomination: 0

Original and historic functions  
and uses: commercial

**DESCRIPTION SUMMARY:**

The old Stevensville Bank is located on the west side of Love Point Road near the center of Stevensville, in Queen Anne's County, Maryland. The building faces the street, with the plain rectangular shed roof structure disguised by an elaborate false front on the east (street) facade. This front is carefully ordered and is decorated with an interesting and eclectic collection of architectural details. The street facade is divided into three bays by four pilasters. In the center bay to either side of the door are single one-over-one windows with molded surrounds and pedimented hoods supported by scrolled brackets. A second story is suggested by a large triple window above the door and smaller four-light windows with crossetted surrounds in the flanking bays. The cornice consists of a broad band of stucco serving as a fascia, with a modest molding below, and an ornate architrave above. One further decorative element on the street facade is a large projecting hood over the entrance door. The interior is divided into a public banking room in the front and an office in the rear. The vault is located in the center at the rear of the front room, and is surrounded by a U-shaped counter with tellers' windows. The walls of this room are decorated with narrow headed wainscot paneling below a plain chairrail. The original ornamental pressed-tin ceiling has survived intact. Also on the property is a frame shed which does not contribute to the significance of the resource.

For General Description, see Continuation Sheet No. 1

QA-264

United States Department of the Interior  
National Park Service

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

Continuation sheet Stevensville Bank  
Queen Anne's County, MD

Item number

7

Page

1

GENERAL DESCRIPTION

The old Stevensville Bank is located on the west side of Love Point Road near the center of Stevensville, in Queen Anne's County, Maryland. It has not served as a bank since it was sold in 1961, but has remained perfectly preserved, and after a recent renovation has been converted into a law office. The renovation consisted almost entirely of necessary repairs and painting, and the building remains virtually untouched both inside and outside.

The building faces the street, with the plain rectangular shed roof structure disguised by an elaborate false front on the east (street) facade. This front is carefully ordered and is decorated with an interesting and eclectic collection of architectural details.

The entire building is covered with stucco except for the first five courses of the foundation. The street facade is divided into three bays by four pilasters. The entrance is located in the center bay and consists of a pair of paneled glass doors. To either side of the door, in the north and south bays, are single one-over-one windows with molded surrounds and pedimented hoods supported by scrolled brackets. Although the building is only one story high, a second story is suggested by a large triple window above the door and smaller four-light windows with crossetted surrounds in the flanking bays. The triple window has a geometric pattern of muntins consisting of diagonals laid over a normal grid pattern.

Horizontal articulation is accomplished by setting the reeded pilasters on high stuccoed bases, and by employing a very wide, bold cornice. The result is a tripartite pattern both horizontally and vertically. The cornice consists of a broad band of stucco serving as a fascia, with a modest molding below, and an ornate architrave above. This is highlighted by a band of egg-and-dart molding, a row of dentil blocks, and scrolled brackets applied below an overhanging soffit. The fascia board above the soffit is relatively narrow and has a simple crown mold applied to it.

The decorative features of the front are carried around both corners of the facade for about five feet, and are terminated by a pair of reeded pilasters.

One further decorative element on the street facade is a large projecting hood over the entrance door which derives support from heavy chains anchored into the wall. It has a wide fascia board cornice decorated with geometric "triglyph" blocks, and closely resembles the marquee hoods found on turn-of-the-century theatres and occasionally on other commercial structures.

The remaining walls of the building are relatively plain by comparison. On the north wall, there is one large window near the east (front) end, and a single door with a plain entrance hood near the west end. The window is unusual in that the upper sash has nine lights, while the lower sash is divided into one row of three small lights above a single large pane of glass. This is

QA-264

United States Department of the Interior  
National Park Service

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

Continuation sheet Stevensville Bank Item number 7 Page 2  
Queen Anne's County, MD

GENERAL DESCRIPTION (continued)

evidently the original configuration, as there are two similar windows symmetrically placed on the rear (west) wall of the building. The south wall is plain except for a large one-over-one window near the center.

The shed roof slopes from north to south, and the eaves on the west wall are finished with a plain rakeboard, while a plain box cornice is carried across the south wall. A brick stove chimney is located on the interior face of the north wall near the rear of the building.

The interior is divided into a public banking room in the front and an office in the rear. The vault is located in the center at the rear of the front room, and is surrounded by a U-shaped counter with tellers' windows. The counter is oak, with raised paneling on the front face. The walls of this room are decorated with narrow beaded wainscot paneling below a plain chairrail and plaster walls above.

The original ornamental pressed-tin ceiling has survived intact. A pair of brass four-light chandeliers is suspended above the tellers' counter.

Also on the property is a frame shed which does not contribute to the significance of the resource.

## 8. Significance

QA-264

| Period                                    | Areas of Significance—Check and justify below    |   |   |  |
|---|--|---|---|--|
| <input type="checkbox"/> prehistoric      | <input type="checkbox"/> archeology-prehistoric  | <input type="checkbox"/> community planning     | <input type="checkbox"/> landscape architecture | <input type="checkbox"/> religion        |
| <input type="checkbox"/> 1400-1499        | <input type="checkbox"/> archeology-historic     | <input type="checkbox"/> conservation           | <input type="checkbox"/> law                    | <input type="checkbox"/> science         |
| <input type="checkbox"/> 1500-1599        | <input type="checkbox"/> agriculture             | <input type="checkbox"/> economics              | <input type="checkbox"/> literature             | <input type="checkbox"/> sculpture       |
| <input type="checkbox"/> 1600-1699        | <input checked="" type="checkbox"/> architecture | <input type="checkbox"/> education              | <input type="checkbox"/> military               | <input type="checkbox"/> social/         |
| <input type="checkbox"/> 1700-1799        | <input type="checkbox"/> art                     | <input type="checkbox"/> engineering            | <input type="checkbox"/> music                  | <input type="checkbox"/> humanitarian    |
| <input type="checkbox"/> 1800-1899        | <input checked="" type="checkbox"/> commerce     | <input type="checkbox"/> exploration/settlement | <input type="checkbox"/> philosophy             | <input type="checkbox"/> theater         |
| <input checked="" type="checkbox"/> 1900- | <input type="checkbox"/> communications          | <input type="checkbox"/> industry               | <input type="checkbox"/> politics/government    | <input type="checkbox"/> transportation  |
|   |  | <input type="checkbox"/> invention              |   | <input type="checkbox"/> other (specify) |

|                |         |                   |         |
|----------------|---------|-------------------|---------|
| Specific dates | c. 1903 | Builder/Architect | unknown |
|----------------|---------|-------------------|---------|

### Statement of Significance (in one paragraph)

Applicable Criteria: A, C  
Applicable Exceptions: none  
Significance Evaluated: local

### SIGNIFICANCE SUMMARY:

The Stevensville Bank is significant for its architecture, and for its role in the commerce of Kent Island and Queen Anne's County. Constructed circa 1903, the Stevensville Bank is the oldest bank building on Kent Island and is among the earliest surviving in the county. The unknown designer combined a variety of classic architectural details into an ordered composition that brings to mind the more formal Beaux Arts bank designs of its period. Although no longer serving as a bank, the building has been carefully maintained and has recently been sensitively restored for use as a law office. The original interior is virtually untouched, with the new office located in the rear, leaving the tellers' counter and vault intact.

For History and Supporting Documentation, see Continuation Sheet No. 3

United States Department of the Interior  
National Park Service

**National Register of Historic Places  
Inventory—Nomination Form**

QA-264

For NPS use only

received

date entered

Stevensville Bank  
Continuation sheet Queen Anne's County, MD

Item number

8

Page

3

HISTORY AND SUPPORT:

The Stevensville Savings Bank of Queen Anne's County was chartered on 4 February 1903. The organizers were Charles Benjamin Downs, founding president, who owned considerable property in the town of Stevensville; Charles Percy Kemp, a physician; Milton Hysore Price and Isaac Grollman, merchants; and John Fletcher Ruth, a farmer. The bank was constructed shortly after that date, on two lots conveyed to the bank corporation 18 December 1903. By 1907, the Bank's financial statement showed assets in excess of \$29,000; the "banking-house, furniture and fixtures" were valued at \$4,301.24. In April 1912 the company's name was changed to Stevensville Bank of Maryland.

The building ceased to be used for banking purposes in 1959, when the company, then known as Tidewater Bank, established a modern facility on the highway southeast of town. The present owner acquired the building in June 1984, and has recently completed a sensitive rehabilitation program, adapting it for use as a law office while retaining all its original furnishings intact.

QA-264

# NATIONAL REGISTER BOUNDARY

DR. CHARLES E. SNYDER  
W.F.W.-11-486

AREA: 0.06 ACRE

BANK BUILDING

SHED

MRS. JENNIE WALLACE

W. H. LOWE

QA-264

STEVENSVILLE BANK  
QUEEN ANNE'S COUNTY,  
MARYLAND

MAP SHOWING SURVEY OF  
A LOT OR PARCEL OF LAND

FOR  
THE STEVENSVILLE BANK OF MARYLAND

Stevensville, Queen Anne's Co., Md.  
Scale: 1"=20' 2-17-61 Shew & Bortlett, Engrs  
Reg-1676

## 9. Major Bibliographical References

QA-264

n/a

## 10. Geographical Data

Acreage of nominated property 0.06 acreQuadrangle name Kent Island, MarylandQuadrangle scale 1:24000

UMT References

A 

|      |   |   |         |   |   |   |          |   |   |   |   |   |   |   |
|------|---|---|---------|---|---|---|----------|---|---|---|---|---|---|---|
| 1    | 8 | 3 | 8       | 6 | 1 | 2 | 0        | 4 | 3 | 1 | 5 | 3 | 8 | 0 |
| Zone |   |   | Easting |   |   |   | Northing |   |   |   |   |   |   |   |

B 

|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
|------|--|--|---------|--|--|--|----------|--|--|--|--|--|--|--|
|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
| Zone |  |  | Easting |  |  |  | Northing |  |  |  |  |  |  |  |

C 

|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
|------|--|--|---------|--|--|--|----------|--|--|--|--|--|--|--|
|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
| Zone |  |  | Easting |  |  |  | Northing |  |  |  |  |  |  |  |

D 

|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
|------|--|--|---------|--|--|--|----------|--|--|--|--|--|--|--|
|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
| Zone |  |  | Easting |  |  |  | Northing |  |  |  |  |  |  |  |

E 

|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
|------|--|--|---------|--|--|--|----------|--|--|--|--|--|--|--|
|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
| Zone |  |  | Easting |  |  |  | Northing |  |  |  |  |  |  |  |

F 

|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
|------|--|--|---------|--|--|--|----------|--|--|--|--|--|--|--|
|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
| Zone |  |  | Easting |  |  |  | Northing |  |  |  |  |  |  |  |

G 

|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
|------|--|--|---------|--|--|--|----------|--|--|--|--|--|--|--|
|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
| Zone |  |  | Easting |  |  |  | Northing |  |  |  |  |  |  |  |

H 

|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
|------|--|--|---------|--|--|--|----------|--|--|--|--|--|--|--|
|      |  |  |         |  |  |  |          |  |  |  |  |  |  |  |
| Zone |  |  | Easting |  |  |  | Northing |  |  |  |  |  |  |  |

Verbal boundary description and justification Boundaries are depicted on the attached plat and comprise the single town lot historically associated with the resource.

List all states and counties for properties overlapping state or county boundaries

|       |     |      |        |      |
|-------|-----|------|--------|------|
| state | n/a | code | county | code |
|-------|-----|------|--------|------|

|       |  |      |        |      |
|-------|--|------|--------|------|
| state |  | code | county | code |
|-------|--|------|--------|------|

## 11. Form Prepared By

name/title Orlando Ridout V, Historic Sites Survey Coordinatororganization Maryland Historical Trustdate 12/14/78; revised 1984street & number 21 State Circletelephone (301) 269-2438

city or town

state


## 12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

☐ national ☐ state ☒ local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature

11-19-84

title

STATE HISTORIC PRESERVATION OFFICER

date

For HCRS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration



UNITED STATES  
DEPARTMENT OF THE ARMY  
CORPS OF ENGINEERS

KENT ISLAND QUADRANGLE  
MARYLAND  
7.5 MINUTE SERIES (TOPOGRAPHIC)

5762 II SW  
(LANGFORD CREEK)

5762 III SE  
(LOVE POINT) 2.2 MI.

17°30"

389

390

1 010 000 FEET

76°15'  
39°00'

CHESTER  
RIVER

4317

4316

420 000  
FEET

QA-264  
STEVENSVILLE BANK  
QUEEN ANNE'S CO.  
MARYLAND  
18-386120-

4315

4315380

GRASONVILLE 2.4 MI.

Stevensville

Wesley Ch

Landing  
Strip

Macum  
Creek

Piney  
Creek

Chester

Kingsley Ch

Landing Field

Cox  
Creek

Creek

Creek

385

5762 III SE  
(LOVE POINT)

387

18

BM 10

13

17

15

16

BM 17

552

BM 7

18

BM 11

8

18

BM 18

4315

QA-264  
Stevensville Bank  
Stevensville  
Private

circa 1903

Constructed circa 1903, the Stevensville Bank is the oldest bank building on Kent Island and among the earliest surviving in the county. The unknown designer combined a variety of classic architectural details into an ordered composition that brings to mind the more formal Beaux Arts bank designs of its period, best expressed by the Centreville National Bank (QA-307). Although no longer serving as a bank, the building has recently been sensitively restored for use as a law office. The original interior is virtually untouched, with the new office located in the rear, leaving the teller's counter and vault intact.

## MARYLAND HISTORICAL TRUST

## INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

**1 NAME**

HISTORIC

Stevensville Bank

AND/OR COMMON

**2 LOCATION**

STREET &amp; NUMBER

West side of Love Point Road

CITY, TOWN

Stevensville

VICINITY OF

CONGRESSIONAL DISTRICT

First

STATE

Maryland

COUNTY

Queen Anne's

**3 CLASSIFICATION**

## CATEGORY

☐ DISTRICT☒ BUILDING(S)☐ STRUCTURE☐ SITE☐ OBJECT

## OWNERSHIP

☐ PUBLIC☒ PRIVATE☐ BOTH

## PUBLIC ACQUISITION

☐ IN PROCESS☐ BEING CONSIDERED

## STATUS

☒ OCCUPIED☐ UNOCCUPIED☐ WORK IN PROGRESS

## ACCESSIBLE

☒ YES: RESTRICTED☐ YES: UNRESTRICTED☐ NO

## PRESENT USE

☐ AGRICULTURE☐ COMMERCIAL☐ EDUCATIONAL☐ ENTERTAINMENT☐ GOVERNMENT☐ INDUSTRIAL☐ MILITARY☐ MUSEUM☐ PARK☐ PRIVATE RESIDENCE☐ RELIGIOUS☐ SCIENTIFIC☐ TRANSPORTATION☒ OTHER: office**4 OWNER OF PROPERTY**

NAME

Mr. and Mrs. Harper M. Smith

Telephone #:

STREET &amp; NUMBER

RT#1, Box 750

CITY, TOWN

Stevensville

VICINITY OF

STATE, zip code

Maryland 21666

**5 LOCATION OF LEGAL DESCRIPTION**

COURTHOUSE,

REGISTRY OF DEEDS, ETC. Queen Anne's County Courthouse

Liber #: CWC 137

Folio #: 422

STREET &amp; NUMBER

Courthouse Square

CITY, TOWN

Centreville

STATE

Maryland 21617

**6 REPRESENTATION IN EXISTING SURVEYS**

TITLE

DATE

☐ FEDERAL ☐ STATE ☐ COUNTY ☐ LOCALDEPOSITORY FOR  
SURVEY RECORDS

CITY, TOWN

STATE

QA-264

**7 DESCRIPTION**

| CONDITION                                     |                                       | CHECK ONE                                     | CHECK ONE   |
|---|---------------------------------------|---|---|
| <input checked="" type="checkbox"/> EXCELLENT | <input type="checkbox"/> DETERIORATED | <input checked="" type="checkbox"/> UNALTERED | <input checked="" type="checkbox"/> ORIGINAL SITE |
| <input type="checkbox"/> GOOD                 | <input type="checkbox"/> RUINS        | <input type="checkbox"/> ALTERED              | <input type="checkbox"/> MOVED                    |
| <input type="checkbox"/> FAIR                 | <input type="checkbox"/> UNEXPOSED    |   | DATE _____  |

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The old Stevensville Bank is located on the west side of Love Point Road near the center of Stevensville. It has not served as a bank since it was sold in 1961, but has remained perfectly preserved, and after a recent renovation has been converted into a law office. The renovation consisted almost entirely of necessary repairs and painting, and the building remains virtually untouched both inside and outside.

The building faces the street, with the plain rectangular shed roof structure disguised by an elaborate false front on the east (street) facade. This front is carefully ordered and is decorated with an interesting and eclectic collection of architectural details.

The entire building is covered with stucco except for the first five courses of the foundation. The street facade is divided into three bays by four pilasters. The entrance is located

CONTINUE ON SEPARATE SHEET IF NECESSARY

## CONTINUATION SHEET

## 7.1 DESCRIPTION

in the center bay, and consists of a pair of paneled glass doors. To either side of the door, in the north and south bays, are single one-over-one windows with molded surrounds and pedimented hoods supported by scrolled brackets. Although the building is only one story high, a second story is suggested by a large triple window above the door and smaller four-light windows with crossetted surrounds in the flanking bays. The triple window has a geometric pattern of muntins consisting of diagonals laid over a normal grid pattern.

Horizontal articulation is accomplished by setting the reeded pilasters on high stuccoed bases, and by employing a very wide, bold cornice. The result is a tripartite pattern both horizontally and vertically. The cornice consists of a broad band of stucco serving as a fascia, with a modest molding below, and an ornate architrave above. This is highlighted by a band of egg-and-dart molding, a row of dentil blocks, and scrolled brackets applied below an overhanging soffit. The fascia board above the soffit is relatively narrow and has a simple crown mold applied to it.

## CONTINUATION SHEET

## 7.2 DESCRIPTION

The decorative features of the front are carried around both corners of the facade for about five feet, and are terminated by a pair of reeded pilasters.

One further decorative element on the street facade is a large projecting hood over the entrance door, which derives support from heavy chains anchored into the wall. It has a wide fascia board cornice decorated with geometric "tryglyph" blocks, and closely resembles the marquee hoods found on turn-of-the-century theatres and occasionally on other commercial structures.

The remaining walls of the building are relatively plain by comparison. On the north wall, there is one large window near the east (front) end, and a single door with a plain entrance hood near the west end. The window is unusual in that the upper sash has nine lights, while the lower sash is divided into one row of three small lights above a single large pane of glass. This is evidently the original configuration, as there are two similar windows symmetrically placed on the rear (west) wall of the building. The south wall is plain except for a large one-over-one window near the center.

The shed roof slopes from north to south, and the eaves on the west wall are finished with a plain

## CONTINUATION SHEET

## 7.3 DESCRIPTION

rakeboard, while a plain box cornice is carried across the south wall. A brick stove chimney is located on the interior face of the north wall near the rear of the building.

The interior is divided into a public banking room in the front and an office in the rear. The vault is located in the center at the rear of the front room, and is surrounded by a U-shaped counter with tellers' windows. The counter is oak, with raised paneling on the front face. The walls of this room are decorated with narrow beaded wainscot paneling below a plain chairrail, and plaster walls above.

The original ornamental pressed-tin ceiling has survived intact. A pair of brass four-light chandeliers is suspended above the tellers' counter.

| PERIOD                             | AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW |   |   |  |
|------------------------------------|--|---|---|--|
| PREHISTORIC                        | <input type="checkbox"/> ARCHEOLOGY-PREHISTORIC  | <input type="checkbox"/> COMMUNITY PLANNING     | <input type="checkbox"/> LANDSCAPE ARCHITECTURE | <input type="checkbox"/> RELIGION            |
| <input type="checkbox"/> 1400-1499 | <input type="checkbox"/> ARCHEOLOGY-HISTORIC     | <input type="checkbox"/> CONSERVATION           | <input type="checkbox"/> LAW                    | <input type="checkbox"/> SCIENCE             |
| <input type="checkbox"/> 1500-1599 | <input type="checkbox"/> AGRICULTURE             | <input type="checkbox"/> ECONOMICS              | <input type="checkbox"/> LITERATURE             | <input type="checkbox"/> SCULPTURE           |
| <input type="checkbox"/> 1600-1699 | <input type="checkbox"/> ARCHITECTURE            | <input type="checkbox"/> EDUCATION              | <input type="checkbox"/> MILITARY               | <input type="checkbox"/> SOCIAL/HUMANITARIAN |
| <input type="checkbox"/> 1700-1799 | <input type="checkbox"/> ART                     | <input type="checkbox"/> ENGINEERING            | <input type="checkbox"/> MUSIC                  | <input type="checkbox"/> THEATER             |
| <input type="checkbox"/> 1800-1899 | <input type="checkbox"/> COMMERCE                | <input type="checkbox"/> EXPLORATION/SETTLEMENT | <input type="checkbox"/> PHILOSOPHY             | <input type="checkbox"/> TRANSPORTATION      |
| <input type="checkbox"/> 1900-     | <input type="checkbox"/> COMMUNICATIONS          | <input type="checkbox"/> INDUSTRY               | <input type="checkbox"/> POLITICS/GOVERNMENT    | <input type="checkbox"/> OTHER (SPECIFY)     |
|                                    |  | <input type="checkbox"/> INVENTION              |   |  |

SPECIFIC DATES

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

Constructed circa 1903, the Stevensville Bank is the oldest bank building on Kent Island and is among the earliest surviving in the county. The unknown designer combined a variety of classic architectural details into an ordered composition that brings to mind the more formal Beaux Arts bank designs of its period, best expressed locally by the Centreville National Bank (QA-307). Although no longer serving as a bank, the building has been carefully maintained and has recently been sensitively restored for use as a law office. The original interior is virtually untouched, with the new office located in the rear, leaving the tellers counter and vault intact.

CONTINUE ON SEPARATE SHEET IF NECESSARY



QA-264

**9 MAJOR BIBLIOGRAPHICAL REFERENCES**

CONTINUE ON SEPARATE SHEET IF NECESSARY

**10 GEOGRAPHICAL DATA**

ACREAGE OF NOMINATED PROPERTY \_\_\_\_\_

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE COUNTY

STATE COUNTY

**11 FORM PREPARED BY**

NAME / TITLE

Orlando Ridout V, Historic Sites Surveyor

ORGANIZATION

Queen Anne's County Historical Society

DATE

12/14/78

STREET & NUMBER

TELEPHONE

CITY OR TOWN

Centreville

STATE

Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust  
The Shaw House, 21 State Circle  
Annapolis, Maryland 21401  
(301) 267-1438

## Queenstown News 1907

Report of the Condition of the  
Stevensville Savings Bank of Queen Anne's County

At Stevensville, in the State of Maryland, at close of  
business May 20, 1907

## Resources

|  |                 |
|--|-----------------|
| Loans and Discounts.....                   | \$16,528.06     |
| Banking-house, furniture and Fixtures..... | 4,301.24        |
| Real Estate & Mortgages Owned.....         | 4,258.60        |
| Due from National Banks.....               | 3,221.88        |
| Due from State Banks.....                  | 53.67           |
| Money in Bank.....                         | <u>1,162.25</u> |
| Total                                      | \$29,525.70     |

## Liabilities

|   |                 |
|---|-----------------|
| Capital Stock paid in.....                    | \$ 9,250.00     |
| Undivided profits, less expenses & taxes..... | 575.45          |
| Due to State Banks.....                       | 745.41          |
| Individual deposits, subject to check.....    | 9,371.82        |
| Savings & Special Deposits.....               | 4,583.02        |
| Bills payable.....                            | <u>5,000.00</u> |
| Total   | \$29,525.70     |

State of Maryland, County of Queen Anne's  
I.G.O. Callaway, Cashier of the above named Bank, do solemnly  
swear that the above statement is true to the best of my  
knowledge and belief.


G.O. Callaway, Cashier

Subscribed and sworn to before me this 28th day of May,  
1907

B.H. Bright, N.P.

Correct: Attes:

C. Percy Kemp  
W.E. Denny  
John F. Ruth, Directors



Love Pt

BM LOVE POINT LANDING

Love Point

BM 16

BM 22

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

BM 16

STEVENSVILLE BANK

QA-264

STEVENSVILLE

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

BM 10

Chester

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

BM 17

CRAB ALLEY BAY

CRAB ALLEY

BAY

CRAB ALLEY

BAY

CRAB ALLEY

BAY

CRAB ALLEY

BAY

CRAB ALLEY

BAY

CHESTER RIVER

Wickes Beach

EASTERN ISLAND

Baybush Pt

Panhandle Pt

Parson Island

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Long Pt

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Hog Island

Narrow Pt

Narrow Pt

Narrow Pt

Narrow Pt

Narrow Pt

Narrow Pt

Narrow Pt

Narrow Pt

Parson Island


Philpots Is.

Long Marsh I

Bodkin Island

QA-264  
Stevensville Bank

Mary McCarthy  
Spring/Summer 2003  
Digital color photo on file at MHT





CA-264 Stevensville Bank, Kent Co.

OR V 1978



Q17-264    Stevensville Bank  
Orlando Ridout v

~~8~~ Feb 1980